

# Smart Grid Test Facility



Suleyman Kahyaoglu  
Jeremy Kramer  
Edward Leung  
Marissa Petersile  
Christopher Powers

# Introduction




- The **Smart Grid Test Facility** is an educational tool for engineering students, allowing them to test various circuitry in a small-scale classroom power grid.
- Traditional energy sources, such as coal, present environmental and non-sustainable threats worldwide.
- In response, the power grid industry has begun turning to clean energy sources and Smart Grid technologies in order to improve efficiency, reliability, and cleanliness of our electricity.






- The **Smart Grid Test Facility** will provide a test environment for basic power grid experiments.
- Students will be able to simulate utility-grade transmission lines with single-phase power flow.
- A real-time data acquisition system will monitor the system's power flow and perform voltage-current analysis from generators to real and reactive loads.
- The Test Facility will provide a safe, user-friendly system with which students can learn about the power grid.
- This system also provides the infrastructure for integration of Smart Grid components by a future project team or class.

# Visualization



- Generation:
    - 12V AC (+/- 5%)
    - 60 Hz (+/- 5%)
    - 3 Generators: Minimum of 2 Motor-Alternator Sets
  - Transmission:
    - Real-world, lumped-element per unit length parameters
    - 3+ lines
  - Loads:
    - R, L, & C binary boxes (1 each)
  - Safety:
    - Generators/pulleys inside isolatable enclosure
  - DAQ:
    - Measure V and I
    - Measure Power Factor and Phase
    - Power Flow Metering
- } +/- 5%


# Level 0 Block Diagram





# Generation System




- Finalization of generation scheme
- Selection and purchase of...
  - 24V, 20A DC Power Supply
  - 24V 1/18HP DC Motor
- Wind Turbine Alternator
- Testing of generation components
- Initiation of design/manufacturing process at EPIC lab
- Funding allocation







# Motor/ Alternator Connection





- Finalization of synchronization and frequency feedback design
- Testing synchronization and feedback designs
- Purchasing of...
  - Another set of motor/alternator
  - Transformers
  - Materials for housing/brackets
  - Encoder
  - Bulbs/switches
- Manufacturing brackets and safety enclosure
- Assembling with all components
- Final testing of components

## Rotary Encoder:


### Purpose:

- Uses photodiode to track motion of concentric casks
- Reports 3-bit information about phase difference of casks.

## MSP430:


### Purpose:

- Feedback Controller
- Takes rotary encoder input and measures  $f$  of generation system.
- Produces PWM signal to drive Buck-Boost converter
- Controlling frequency through voltage/torque/frequency relationship.



# Transmission Lines

- Transmission Line Final Values
- Breadboard to PCB Conversion: Altium Designer Summer '09
- Digikey surface-mount components purchased
  - R, C, Switches, Terminal Blocks
- Footprints placed for 10/25/25/50 mile (4) line simulation



# Data Collected




- Length of lines decreased to fit actual distances  $< 50$  mi.
- Capacitance values remain low, nF level
- Verified RLCs with utility professionals
- Minimum resistance per line:  $1.1\Omega$
- Generator-to-generator: 35/50/60/75 mile net distances

TRANSMISSION LINE CHARACTERISTICS		
R ( $\Omega/\text{mi}$ )	L (mH/mi)	C (nF/mi)
0.1128	1.329	22

FINAL TRANSMISSION LINE SPECS				
TL No.	Length (mi)	R ( $\Omega$ )	L (mH)	C (nF)
1	10	1.1	13.3	220
2	25	2.8	33.2	550
3	25	2.8	33.2	550
4	50	5.6	66.5	1100

- In order to complete the transmission lines, the parts must be soldered to the PCBs.
  - This includes resistors, inductors, capacitors, terminal blocks, and switches.
- The PCBs must be integrated into the system by being affixed to the cart.



# Loads



## Binary Load Box:

### Resistive:

- Design: completed and tested

### Capacitive/Inductive:

- Design: completed and tested

### Luminous Loads:

- Design: completed



## A New Approach:

### Citgo Sign:

- Previous Issues
  - Wiring - untenable
  - Power Requirements - unnecessarily complicated
- Solution
  - Scaling back LED's – ~14 down from 40+
  - Use of Clear Acrylic Façade

### Hobby Lights & Motors:

- Scrapped for Cost

### Magnetic Loads:

- Scrapped for Cost



## Binary Load:

- Resistive:
  - Draw/Acquire/Test PCB
- Capacitive/Inductive:
  - Draw/Acquire/Test PCB

## Citgo Sign:

- Draw/Acquire/Test PCB
- Machine Façade


# Data Acquisition System



## Current and Voltage Interfaces Prototyped

- JFET op-amps -> minimize noise and input biasing
- ASC712 Hall Effect Sensor
- SMD parts selected for PCB fabrication

## Basic Functionality MATLAB code prepared

- Phase
- Magnitudes
- RMS values
- Power Factor





Note: Noisy Ground

## Remaining Work:

- Create PCBs
- Continue MATLAB work
  - Power Flow
  - GUI
- Integrate/Final Testing

# Project Planning

# Gantt Chart



ID	Task Mode	Task Name	Duration	Start	Finish	Timeline																
						Dec 7, '14			Dec 28, '14			Jan 18, '15			Feb 8, '15			Mar 1, '15			Mar 22, '15	
				F	S	S	M	T	W	T	F	S	S	M	T	W	T	F	S	S	M	T
1	DAQ	(DAQ) Program Data Processing	34 days	Mon 12/1/14	Thu 1/15/15																	
2	DAQ	(DAQ) Test Data Processing	11 days	Fri 1/16/15	Fri 1/30/15																	
3	DAQ	(DAQ) Program and Test GUI	20 days	Tue 2/10/15	Fri 3/6/15																	
4	DAQ	(DAQ) Pick Components	17 days	Tue 12/2/14	Wed 12/24/14																	
5	DAQ	(DAQ) Design Interface Circuits	11 days	Thu 1/1/15	Thu 1/15/15																	
6	DAQ	(DAQ) Test Interface Circuits	11 days	Fri 1/16/15	Fri 1/30/15																	
7	DAQ	(DAQ) PCB Layout	11 days	Fri 2/20/15	Thu 3/5/15																	
8	DAQ	(DAQ) PCB Fabrication	11 days	Fri 3/6/15	Fri 3/20/15																	
9	DAQ	(DAQ) Project Integration	7 days	Mon 3/23/15	Tue 3/31/15																	
10	Generation	(Generation) Select Components	30 days	Tue 1/20/15	Sun 3/1/15																	
11	Generation	(Generation) Test Components	40 days	Tue 1/20/15	Fri 3/13/15																	
12	Generation	(Generation) Design Feedback and Synchronization System	24 days	Tue 1/20/15	Fri 2/20/15																	
13	Generation	(Generation) Pick Feedback and Synchronization Components	11 days	Mon 2/23/15	Fri 3/6/15																	
14	Generation	(Generation) Feedback and Synchronization Testing	10 days	Mon 3/9/15	Fri 3/20/15																	
15	Generation	(Generation) Design Enclosure	6 days	Mon 3/2/15	Mon 3/9/15																	
16	Generation	(Generation) Construct Enclosure	9 days	Tue 3/10/15	Fri 3/20/15																	
17	Generation	(Generation) Project Integration	7 days	Mon 3/23/15	Tue 3/31/15																	
18	Transmission	(Transmission) Integration Design	56 days	Mon 12/1/14	Mon 2/16/15																	
19	Transmission	(Transmission) Select RLC Components	18 days	Mon 12/1/14	Wed 12/24/14																	
20	Transmission	(Transmission) PCB Layout	37 days	Fri 1/9/15	Sun 3/1/15																	
21	Transmission	(Transmission) PCB Fabrication	15 days	Mon 3/2/15	Fri 3/20/15																	
22	Transmission	(Transmission) Project Integration	6 days	Mon 3/23/15	Mon 3/30/15																	
23	Load	(Load) Load Selection and Testing	45 days	Mon 12/1/14	Fri 1/30/15																	
24	Load	(Load) PCB Design	11 days	Mon 2/23/15	Fri 3/6/15																	
25	Load	(Load) PCB Fabrication	10 days	Mon 3/9/15	Fri 3/20/15																	
26	Load	(Load) Project Integration	4 days	Thu 3/26/15	Tue 3/31/15																	
27		Project Functional Testing	0 days	Wed 4/1/15	Wed 4/1/15																	
28		Final Preparation/Details	9 days?	Thu 4/2/15	Tue 4/14/15																	
29		Delivery Day	0 days	Wed 4/15/15	Wed 4/15/15																	
30		ECE Day	0 days	Tue 5/5/15	Tue 5/5/15																	

# Budget



Componential Description		Est. Price
Generation	Motors	\$300
	Alternators	\$300
	Transformers	\$50
	Feedback System	\$30
	Synchronization System	\$30
	Enclosure/Bracket Materials	\$300
		Total: \$1010
Transmission Lines	PCB	\$50
	Passive RLC	\$70
	Additional Parts	\$30
	Total: \$150	
Generic Loads	Passive Loads	\$175
	Display Loads	\$75
	PCB	\$50
	Total: \$300	
Data Acquisition	DAQ	\$120
	Sensor Boards	\$75
	PCB	\$35
	Power Supply	\$35
		Total: \$265
Net Total: \$1725		
ECE Funding: \$350		
KHC Funding: \$400		
Budgetary Total: \$975		

